




INSIDE VIEW BC20B




FRONT VIEW BC20B



BOTTOM VIEW BC20B



END VIEW
TYPICAL



SECTION VIEW
SCALE: $\frac{3}{16}'' = 1''$

BILL OF MATERIALS			
PART NO.	QTY.	DESCRIPTION	MAT'L. SPEC.
1A	66	50. FT. OF PLATE, (6mm) THK	JIS G3101 SS400
2C	90	50. FT. OF SHEET, 12 GA (3mm) THK.	A240 TP309S
3A	7	LN. FT. OF BEAM, H150x75x5x7	JIS G3101 SS400
8B	653	50. FT. OF INSULATION, 2" THK, 8# DENSITY	SUPERWOL PLUS

PART NUMBERS ARE TO HAVE THE PREFIX OF "BC". FOR EXAMPLE, "20B" (ASSEMBLY) + "1A" (PART NUMBER) WOULD BE "BC20B1A"

GENERAL NOTES:

1. SEE V17494-MANC-0001 FOR "EQUIPMENT SPECIFICATION FOR SHOP FABRICATED MODULE BOX ASSEMBLY FOR HEAT RECOVERY STREAM GENERATOR."
2. ALL STEEL WORK SHALL COMPLY WITH THE AMERICAN INSTITUTE OF STEEL FABRICATION (AISC) SPECIFICATIONS FOR THE DESIGN, FABRICATION, AND ERECTION OF STRUCTURAL STEEL.
3. PROVIDE $\frac{3}{4}$ " (19mm) DIA. DRAIN HOLES IN STRUCTURALS WHERE NECESSARY TO ENSURE WATER DRAINAGE DURING SHIPMENT AND AFTER ERECTION.
4. ALL BOLT HOLES ARE TO BE PUNCHED OR DRILLED.
5. TRIM LINER & WASHERS WITH $\frac{1}{4}$ " CLEARANCE AROUND BEAM LUGS AT TIME OF ASSEMBLY.
6. ALL WELDING TO BE DONE IN ACCORDANCE WITH AWS D1.1 STRUCTURAL WELDING CODE, CURRENT EDITION USING E70XX ELECTRODES. VENDOR IS RESPONSIBLE FOR THE WELD END PREPARATION OF ALL FIELD WELDS.
7. SEAL WELD ALL STRUCTURALS TO CASING AND OTHER STRUCTURALS. PRESSURE CASING TO BE SEAL WELDED GAS TIGHT.
8. ALL WELDS TO BE P1-P1 UNLESS NOTED OTHERWISE.
9. ALL INSULATION TO BE COMPRESSED APPROX. $\frac{1}{8}$ " PER 1" TO GIVEN THICKNESS.
10. ● DENOTES STUDS TO HAVE WASHER AND NUT FINGER TIGHT ONLY. DO NOT TACK WELD UNTIL AFTER FIELD LINERS AND CONNECTIONS ARE MADE IN THE FIELD.
11. TOTAL APPROX. WEIGHT:
BC40B: 12,403 lbs. / 5,626 kg.
WEIGHT MAY BE GREATER IF INSULATION IS WET.
12. QUANTITIES SHOWN ARE FOR ONE (1) UNIT:
-(1) ONE UNIT REQUIRED FOR MIDDLETOWN PROJECT.
-(1) ONE UNIT REQUIRED FOR KING MOUNTAIN PROJECT.
13. IMPERIAL DIMENSIONS TAKE PRECEDENCE OVER METRIC. METRIC DIMENSIONS ARE TO BE VERIFIED TO THE IMPERIAL BEFORE USE.


REFERENCE DRAWINGS:

- V17494-BCND-0020 - BOTTOM CASING BOX 2 (BC20A & BC20C)
V17494-BCND-0022 - BOTTOM CASING BOX 1 THRU
BOX 2 DETAILS
V17494-BCND-0023 - BOTTOM CASING BOX 1 THRU
BOX 2 DETAILS
V17494-BCND-0090 - STANDARD CASING & LINER DETAILS
V17494-EBND-0103 - STANDARD FABRICATION TOLERANCES
FOR TOP AND BOTTOM CASINGS

00	FIRST ISSUE	4-DEC-15	SK/TA	JONES	-				FRY
Rev.	Description	Date	Drawn	Chkd.	Chkd.				Appr.

This drawing contains Vogt Power International's confidential and proprietary information and cannot be used, duplicated or disclosed in whole or in part, except with the express written permission of Vogt Power International. EXCEPT AS EXPRESSLY STATED IN ANY WRITTEN CONTRACT - ALL WARRANTIES RELATING TO THIS DRAWING, INCLUDING THE WARRANTIES OF MERCHANTABILITY AND FITNESS, ARE DISCLAIMED.

© Vogt Power International, Inc. All rights reserved as an unpublished work.

MIDDLETOWN ENERGY CENTER and KINGS MOUNTAIN ENERGY CENTER for NTE ENERGY and GEMMA POWER SYSTEMS	 Scale:
VOGT POWER PROJECTS V17494 & V17495	1/2" = 1'-0"

Title	BOTTOM CASING BOX2 BC20B
-------	--------------------------------



Internal Drawing Status	Size	Drawing No.	Rev.
FOR RECORD	D	V17494-BCND-0021	00