



MECKMEC
superceded by ME stamped drawings

REPLACE HOIST RING W/
HB78X112SS 7/8"x1 1/2" H.S.
BOLT WITH FW78P 7/8" FLAT
WASHER AND K78RW 7/8"
RUBBER WASHER.



**TYPE 'S' BUILDING
DETAIL AT ROOF**




WELD

MATERIAL LIST (PARTS TO SHIP W/ BUILDING)

PART NO.	DESCRIPTION
HB78X112SS	7/8" x 1 1/2" BOLT (STAINLESS) TYPE 'S'
HB78X2SS	7/8" x 2" BOLT (STAINLESS) TYPE 'AL'
K78RW	7/8" RUBBER WASHER
FW78P	7/8" FLAT WASHER

MATERIAL LIST

PART NO.	DESCRIPTION
HR78	7/8" HOIST RING (7,500#)
PLATE30K	30K-LIFT TOP PLATE WITH WELDED NUT
78BKTR-B7	7/8" THREADED ROD
HN78C	7/8" HEAVY HEX NUT
CN78	7/8" GRADE 2H HEAVY HEX COUPLER



**BASE DETAIL
TYPE 'S' AND 'AL' BUILDINGS**

VOGT POWER INTERNATIONAL
V17494-BEXD-5109-01
12-Jul-2016

NOTE:

- CUTTING OF THREADED ROD REQUIRED TO ACHIEVE CORRECT LENGTH. HIGH SIDE IS TALLER THAN LOW SIDE (ON SINGLE SLOPE BUILDINGS ONLY).
- SITE WORK** AFTER BUILDING IS SET AND ANCHORED REMOVE HOIST RING WITH A 3/4" ALLEN HEAD WRENCH (NOT PROVIDED BY PARKLINE). REPLACE WITH HB78X112SS 7/8" BOLT, FW78P 7/8" FLAT WASHER AND K78RW 7/8" RUBBER WASHER (FOR TYPE 'S' BUILDINGS). FOR TYPE 'AL' BUILDINGS, REMOVE TOP BEVELED WASHER AND APPLY CAULK TO AREA THAT BEVELED WASHER SETS. RE-INSTALL BEVELED WASHER, HB78X2SS 7/8" BOLT, FW78P 7/8" FLAT WASHER AND K78RW 7/8" RUBBER WASHER.
- EACH SIDE WALL WALL CAP SPLICE MUST BE REINFORCED WITH #774A CAP SPLICE. THIS APPLIES TO ALL 'S' TYPE SIDE WALL CAPS.
- ROOF LIFTING SYSTEM FOR BUILDINGS WEIGHING UP TO 30,000 IBS MAXIMUM.

REVISIONS	BY
5/8/2014	BMM
09-28-15	DJM

PARKLINE, INC.
RT. 62, ELEANOR INDUSTRIAL PARK
ELEANOR, WV 25070
EMAIL: PARKLINE@PARKLINE.COM
PHONE: 800-786-4855
FAX: 304-586-3842
ENGINEER: TOM HARDING
THARDING@PARKLINE.COM



**30K LIFTING SYSTEM
FOR TYPE 'S' AND 'AL'
BUILDINGS**

INSTALLATION DETAILS

DATE 5-17-2013

DRAWN BY KRK

SCALE NTS

ORDER NO.

REVISION 2

30K-LIFT